



DOUBLE CHECK VALVE ASSEMBLY (SECTION)

NOT TO SCALE

NOTES:

1. THE BACKFLOW ASSEMBLY SHALL BE AN APPROVED ASSEMBLY AS SHOWN ON THE WASHINGTON STATE APPROVAL LISTING.
2. BACKFLOW ASSEMBLY INSTALLATION SHALL BE IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS AND MEET THE MINIMUM STANDARDS OF THE UNIFORM PLUMBING CODE.
3. BACKFLOW ASSEMBLY SHALL BE CENTERED WITHIN THE ENCLOSURE AND PROVIDE MINIMUM HORIZONTAL AND VERTICAL CLEARANCE AS REQUIRED.
4. THE BACKFLOW ASSEMBLY SHALL BE INSTALLED IMMEDIATELY BEHIND THE WATER METER ON PRIVATE PROPERTY. INSTALLATION OF THE BACKFLOW ASSEMBLY INTERNAL TO THE BUILDING WILL NOT BE ALLOWED. SEE DISTRICT SPECIFICATIONS FOR ADDITIONAL INFORMATION.
5. THE BACKFLOW ASSEMBLY IS TO BE TESTED AT INSTALLATION AND ANNUALLY THEREAFTER. THE TEST SHALL BE PERFORMED BY A CERTIFIED WASHINGTON STATE BACKFLOW ASSEMBLY TESTER. FOR A LIST OF CERTIFIED TESTERS, PLEASE CONTACT THE DISTRICT UTILITY SPECIALIST, WATER QUALITY AT (425) 654-6321. A COPY OF THE TEST REPORT SHALL BE SENT TO THE FOLLOWING EMAIL ADDRESS:

BACKFLOW@NUD.NET

**DOUBLE CHECK VALVE ASSEMBLY
GENERAL INSTALLATION GUIDELINES**

NOT TO SCALE

DETAIL APPROVALS
EDITOR TMC
MANAGER SJD

NORTHSHORE UTILITY DISTRICT
 2021 STANDARD WATER DETAILS

14a

LAST UPDATED
APRIL 2021