



**MATERIALS LIST**

ITEM QTY. DESCRIPTION

- ① 1 TAPPED & THREADED D.I. CAP, RJ WITH 2" IP TAP.
- ② 2 2" GALVANIZED PIPE, LENGTH TO FIT.
- ③ 1 2" 90° GALVANIZED ELBOW, FIPxFIP.
- ④ 1 2" BALL VALVE, FIPxFIP, MATCO 757T08LF OR EQUAL.
- ⑤ 1 TRAFFIC RATED BOX AND COVER, OR EQUAL.

NOTES:

1. NUMBER AND LOCATION OF THE TEMPORARY BLOW-OFFS WILL BE AS SHOWN ON THE DESIGN PLANS OR AS DIRECTED BY THE DISTRICT IN THE FIELD.
2. PROVIDE TEMPORARY BLOCKING FOR BLOW-OFFS TO RESIST TEST PRESSURES.

**TEMPORARY BLOW-OFF ASSEMBLY  
FOR NEW WATERMAIN**

NOT TO SCALE

**DETAIL APPROVALS**

**EDITOR** TMC

**MANAGER** SJD

**NORTHSHORE UTILITY DISTRICT**

2021 STANDARD WATER DETAILS

**17**

LAST UPDATED  
FEBRUARY 2020