



#### NOTES:

1. THIS SIDE SEWER CONNECTION IS ONLY ALLOWED FOR CONSTRAINED SITES AS DETERMINED BY THE DISTRICT. FOR ALL OTHER SIDE SEWER CONNECTIONS, SEE STANDARD SEWER DETAIL 7.
2. A SIDE SEWER PERMIT MUST BE OBTAINED FOR SIDE SEWER CONNECTION FROM WYE TO BUILDING FOUNDATION.
3. PROVIDE DETECTOR TAPE 24" ABOVE PIPE BEDDING FOR ENTIRE LENGTH OF STUB AND INTO THE CLEANOUT BOX.
4. PIPE BEDDING TO BE PEA GRAVEL PER STANDARD SEWER DETAIL 11.
5. ALL PIPE TO BE AT 2% MINIMUM SLOPE.

## SIDE SEWER STUB CONNECTION FOR CONSTRAINED SITES

NOT TO SCALE

#### DETAIL APPROVALS

EDITOR *TMC*

MANAGER *SJD*

## NORTHSHORE UTILITY DISTRICT

### 2023 STANDARD SEWER DETAILS

**7a**

LAST UPDATED  
JANUARY 2023