



PROFILE VIEW

NOTES:

1. THIS SIDE SEWER CONNECTION IS ONLY ALLOWED FOR CONSTRAINED SITES AS DETERMINED BY THE DISTRICT. FOR ALL OTHER SIDE SEWER CONNECTIONS, SEE STANDARD SEWER DETAIL 7.
2. A SIDE SEWER PERMIT MUST BE OBTAINED FOR SIDE SEWER CONNECTION FROM WYE TO BUILDING FOUNDATION.
3. PROVIDE DETECTOR TAPE 24" ABOVE PIPE BEDDING FOR ENTIRE LENGTH OF STUB AND INTO THE CLEANOUT BOX.
4. PIPE BEDDING TO BE PEA GRAVEL PER STANDARD SEWER DETAIL 11.
5. ALL PIPE TO BE AT 2% MINIMUM SLOPE.

**SIDE SEWER STUB CONNECTION
FOR CONSTRAINED SITES**

NOT TO SCALE

DETAIL APPROVALS	
EDITOR	TMC
MANAGER	SJD

**NORTHSHORE UTILITY DISTRICT
2024 STANDARD SEWER DETAILS**



LAST UPDATED
JANUARY 2023